Pre-installation guide

Prepare your installation space before delivery. This guide covers the flat-pack Finnish sauna cabins with their own integral floor.

PLAN FOR YOUR SAUNA AND HEATER

Read this guide alongside the assembly instructions and the manual for the supplied heater. Confirm the model-specific space and electrical requirements before installation.

01 Space for assembly and final positioning

The sauna arrives **flat-packed for assembly in its destination room**. Allow working space around the cabin during assembly, then move it into its final position.

Check the delivery route and available room dimensions in advance. When positioning the cabin, follow the clearance and safety-distance requirements in the sauna and heater instructions.

02 A flat, level and stable base

The sauna is a **free-standing, fully enclosed cabin with its own integral floor**. It is designed for indoor installation.

The cabin must be fully supported on a **flat, level and firm base**. Once assembled, it must sit securely and remain stable without rocking or movement.

03 Electrical preparation

Arrange electrical preparation with a **qualified electrician**. Cable type, number of cores, conductor size and protective devices must suit the supplied heater, its power rating and the installation instructions.

Leave approximately **3-4 metres of spare cable** at the sauna location for connection. Confirm the cable route and final connection requirements with your electrician before installation.

Provide suitable **RCD (Residual Current Device) protection**. A local **rotary isolation switch** beside the sauna is also recommended so the equipment can be isolated for servicing.

This preparation guide does not replace the model-specific installation instructions. If any requirements differ or are unclear, contact Crystal Bathroom before installation.